

AD-A058 847


NEW JERSEY STATE DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/6 13/2
NATIONAL DAM SAFETY PROGRAM. WESTONS MILLS ARCH DAM (NJ 00382),--ETC(U)
AUG 78 F K JOLLS

DACW61-78-C-0124

NL

UNCLASSIFIED

1 of 1
AD
A058 847



Approved for public release;
distribution unlimited

LEVEL

(1)

RARITAN RIVER BASIN

LAWRENCE BROOK, MIDDLESEX COUNTY

NEW JERSEY


WESTONS MILLS ARCH DAM

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

AD A058847

DDC FILE COPY

NJ 00382



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE - 2D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

05 223

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00382	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Westons Mills Arch Dam Middlesex County, N.J.		5. TYPE OF REPORT & PERIOD COVERED (9) FINAL rept.
7. AUTHOR(s) F. Keith Jolls P.E.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Louis Berger & Associates Inc. 100 Halsted St. East Orange, N.J.		8. CONTRACT OR GRANT NUMBER(s) DACW61-78-C-0124
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, Pennsylvania 19106		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS (12) 64p.
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE Aug 78
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited. National Dam Safety Program. Westons Mills Arch Dam (NJ00382), Raritan River Basin, Lawrence Brook, Middlesex County, New Jersey. Phase I. Inspection Report.		
17. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited. National Dam Safety Program. Westons Mills Arch Dam (NJ00382), Raritan River Basin, Lawrence Brook, Middlesex County, New Jersey. Phase I. Inspection Report.		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia, 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams--New Jersey National Dam Safety Program Phase I Dam Safety Westons Mills Arch Dam N.J.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's ade- quacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		

DDC
RECEIVED
SEP 19 1978
F

NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED US BY
THE SPONSORING AGENCY. ALTHOUGH IT
IS RECOGNIZED THAT CERTAIN PORTIONS
ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.

ACCESSION for	
NTIS	White Section <input checked="" type="checkbox"/>
DOC	B.M. Section <input type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
DISTRIBUTION	
BY	
DISTRIBUTION/AVAILABILITY CODES	
DI	SPECIAL
A	



IN REPLY REFER TO

NAPEN-D

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE - 2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

80 AUG 1978

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Westons Mills Arch Dam in Middlesex County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given on the first four pages of the report.

Based on visual inspection, available records, calculations and past operational performance, Westons Mills Arch Dam, initially listed as a high hazard potential structure but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in fair overall condition. However, the dam's spillway is considered seriously inadequate since 9 percent of the Spillway Design Flood (SDF) would overtop the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more precise and sophisticated methods procedures and studies within six months from the date of approval of this report. Any practicable remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1979.

b. Within six months of the date of approval of this report, the owner should initiate necessary engineering studies to determine the foundation conditions and assess the structural stability of the dam. The studies should address the possible effects of the collapse of the dam downstream on the subject dam. These studies should also include a determination of the need to repair the destroyed sluice gate. Any remedial measures found necessary, should be initiated in calendar year 1979.

NAPEN-D

Honorable Brendan T. Byrne

c. During the next period of low flow, the reservoir should be drawn down as necessary to investigate the extent of spalling and surface deterioration of the concrete. Any remedial actions found necessary, should be initiated within six months of the drawdown.

d. Within one year of the date of approval of this report, the following actions should be initiated.

(1) Berms behind the abutments should be raised to at least abutment height and both the berms and abutments should be furnished with slope protection.

(2) Large debris and fallen trees should be removed from the upstream channel and reservoir.

(3) Initiate a system for recording operation and maintenance procedures.


A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressmen Frank Thompson, Jr. and Edward Patton of the Fourth and Fifteenth District, respectively. Under the provisions of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, thirty days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia, 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely yours,

1 Incl
As stated


JAMES G. TON
Colonel, Corps of Engineers
District Engineer

Cy furn:
Mr. Dirk C. Hofman, P.E.
Department of Environmental Protection

WESTONS MILLS ARCH DAM (NJ00382)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 14 and 17 June 1978 and 19 July 1978 by Louis Berger and Associates, Inc. under contract to the State of New Jersey. The state, under agreement with the U. S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Westons Mills Arch Dam, initially listed as a high hazard potential structure but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in fair overall condition. However, the dam's spillway is considered seriously inadequate since 9 percent of the Spillway Design Flood (SDF) would overtop the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more precise and sophisticated methods, procedures and studies within six months from the date of approval of this report. Any practicable remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1979.

b. Within six months of the date of approval of this report, the owner should initiate necessary engineering studies to determine the foundation conditions and assess the structural stability of the dam. The studies should address the possible effects of the collapse of the dam downstream on the subject dam. These studies should also include a determination of the need to repair the destroyed sluice gate. Any remedial measures found necessary, should be initiated in calendar year 1979.

c. During the next period of low flow, the reservoir should be drawn down as necessary to investigate the extent of spalling and surface deterioration of the concrete. Any remedial actions found necessary, should be initiated within six months of the drawdown.

d. Within one year of the date of approval of this report, the following actions should be initiated.

(1) Berms behind the abutments should be raised to at least abutment height and both the berms and abutments should be furnished with slope protection.

(2) Large debris and fallen trees should be removed from the upstream channel and reservoir.

(3) Initiate a system for recording operation and maintenance procedures.

APPROVED: _____

James G. Ton
JAMES G. TON
Colonel, Corps of Engineers
District Engineer

DATE: _____

30 Aug 78

PHASE I REPORT
NATIONAL DAM INSPECTION PROGRAM

Name of Dam Westons Mills Arch Dam NJ 00382

- State New Jersey
County Located Middlesex
Coordinates Lat.4029.0 - Long.7424.9
Stream Lawrence Brook
Date of Inspection 19 June 1978

ASSESSMENT OF
GENERAL CONDITIONS


Westons Mills Arch Dam is in fair condition but the spillway is seriously inadequate. Little engineering information is available and it is recommended that the owner provide, in the near future, detailed foundation investigations and engineering studies. Remedial actions recommended are:

- Construction of slope protection around the abutments.
- Removal of large debris in the upstream channel.


The spillway capacity for the downgraded significant hazard category is 8 percent of the design flood. No appreciable improvement can be made to the existing spillway capacity. A collapse of the Lower Dam 600 feet downstream could endanger the Westons Mills Arch Dam by causing a sweepout of the downstream channel riprap.



F. Keith Jolls P.E.
Project Manager



Rudolph Wrubel
Vice President, Engineering



JUNE 1978

OVERVIEW OF WESTONS MILLS ARCH DAM

TABLE OF CONTENTS

	<u>Page</u>
Assessment of General Conditions	
Overall View of Dam	
Section 1 - Project Information	1-4
Section 2 - Engineering Data	5-7
Section 3 - Visual Inspection	8-9
Section 4 - Operational Procedures	10
Section 5 - Hydraulic/Hydrologic	11-13
Section 6 - Structural Stability	14-15
Section 7 - Assessment/Recommendations/ Remedial Measures	16-18

FIGURES

- Figure 1 - Regional Vicinity Map
- Figure 2 - General Plan and Sections of Dam

APPENDIX

Check List - Visual Inspection	
Check List - Engineering Data	
Photographs	
Check List - Hydrologic and Hydraulic Data	
Computations	A1-A17

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
NAME OF DAM: WESTONS MILLS ARCH DAM NJ 00382

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority

This report is authorized by the Dam Inspection Act, Public Law 92-367, and has been prepared in accordance with contract FPM-36 between Louis Berger & Associates, Inc. and the State of New Jersey and its Department of Environmental Protection, Division of Water Resources. The State, in turn, is under agreement with the U.S. Army Corps of Engineers, Philadelphia to have this inspection performed.

b. Purpose of Inspection

The purpose of this inspection is to evaluate the structural and hydraulic condition of the Westons Mills Arch Dam and appurtenant structures, and to determine if the dam constitutes a hazard to human life or property.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

Westons Mills Arch Dam is a unreinforced concrete arch dam with three sluice gates on the west end. Each gate consists of a 30 inch cast iron pipe with a hand cranked sluice gate bolted to its face. The spillway extends across the entire length of the crest. The crest of the dam is 200 feet long, with a radius of 160 feet. At each end there is a concrete abutment 24 feet by 10 feet with a top elevation 2.5 feet above the spillway

crest. The height from spillway crest to the downstream channel invert is about 9 feet.

b. Location

Westons Mills Arch dam is located at Westons Mills, in the City of New Brunswick, Middlesex County: 0.5 miles northwest of Interchange 9 of the New Jersey Turnpike. It is immediately south of the concrete arch bridge carrying Route 18 over Lawrence Brook.

c. Size Classification

The maximum height of the dam is approximately 17 feet and the conservation storage is estimated to be 1050 acre feet. Therefore the dam is in the intermediate size category.

d. Hazard Classification

The dam was originally classified as a high hazard by the Corps of Engineers but as a result of this inspection, it is recommended that it be downgraded to a significant hazard classification. The town of Westons Mills lies immediately downstream; however, the residential areas are approximately 20 to 30 feet above the elevation of the dam and should failure occur, it appears there would be only minor property damage, principally involving boating facilities. The bridge to the immediate north (on Burnet Street) which spans Lawrence Brook and the Route 18 bridge just below the dam would probably not be harmed should this dam fail.

e. Ownership

The dam is owned by the City of New Brunswick, City Hall, 78 Bayard Street, New Brunswick, New Jersey 08903.

f. Purpose of Dam

The dam is used to increase the reservoir capacity for the city water supply system.

g. Design and Construction History

Westons Mills Arch Dam was designed by F. W. Schwierts Co. and constructed by the B. C. Coon Construction Company of Luzerne, Pennsylvania. Construction was completed in January 1919.

h. Normal Operating Procedures

A water supply intake dam exists 600 feet downstream and the only operations carried on at Westons Mills Arch dam is to regulate the lower reservoir elevation during periods of low flow.

1.3 PERTINENT DATA

a. Drainage Area

The drainage area for the Westons Mills Arch Dam is 42.0 square miles.

b. Total spillway capacity at maximum pool elevation - 2290 c.f.s.

c. Elevation (M.S.L.)

Top of dam	-	21.09
Maximum pool	-	21.09
Recreation	-	18.43

d. Reservoir

Length of maximum pool	-	13500 feet
Length of recreation pool	-	12600 feet

e. Storage

Recreation pool	-	1050 acre feet
Top of dam	-	1600 acre feet

f. Reservoir Surface

Top of dam	-	180 acres
Maximum pool	-	180 acres
Recreation pool	-	160 acres
Spillway crest	-	160 acres

g. Dam

Type - Concrete arch dam
Length - 248 feet
Height - 17 feet (9 feet - spillway crest to downstream invert)
Top width - 3 feet
Zoning - No zoning information available

h. Diversion and Regulating Tunnel

None

i. Spillway

Type - narrow crest (radial)
Length of weir - 200 feet
Crest elevation - 18.43 feet

j. Regulating Outlets

Three 30 inch diameter pipes with sluice gates attached.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

The information available for review of the Westons Mills Arch Dam included:

- 1) Drawing entitled "Plan for Arched Dam" dated June 19, 1917, together with bidding documents and specifications (partially complete).
- 2) 1917-1919 correspondence between the City Engineer and the Consulting Engineer (numerous letters).
- 3) Partial stress calculations made by Consulting Engineer, F. W. Schwiers Jr. Co., 90 West Street, New York.
- 4) Photographs of dam during and after construction, 1918-1919.

2.2 CONSTRUCTION

The information regarding the original construction included photographs, progress reports and correspondence between the City Engineer and Consulting Engineer indicates the work was carried on in a controlled workmanlike fashion. The dam was built by the B. C. Coon Construction Company of Luzerne, Pennsylvania. An additional 18 inches of height was added to the contract plan height during construction when it was recorded that the rock bedding on which the dam is founded was located about one foot higher than the original plan elevation.

The dam immediately downstream was constructed prior to the study dam and replaced a wood structure which burned down.

2.3 OPERATION

See Section 4. An inspection was ordered by the New Jersey Bureau of Water Control in 1968 but according to Bureau correspondence of 3 August 1973 to Robert

C. Kane, City Engineer, the inspection had not been carried out as of that date. No records of subsequent inspections were located.

2.4 EVALUATION

a. Availability

The original engineering data reviewed indicates that the construction was carefully prosecuted and proper supervision was in evidence. Additional information required for a complete evaluation should include:

- 1) Concrete cores for strength evaluation.
- 2) Visual inspection (dewatering or with divers) of the dam foundations.

b. Adequacy

The concrete mix specified was 1:2.5:5 and in light of the visible portions viewed during the field inspection, was properly mixed and placed. No attempt was formulated in this phase regarding the present compressive strength. From a summary of quantities in the 1917 bid documents, the arch structure is not reinforced, hence shrinkage cracks could be expected in the arch ring.

The foundation conditions for this dam consist of a shallow depth of fine granular and fine grained material overlying shale bedrock. The dam is founded on the shale according to the design plans. It is unknown whether the base was keyed into the rock or cast directly on the surface.

The overburden soil is a silty sand to sandy silt with varying amounts of intermixed gravel. The depth to bedrock is estimated at less than ten feet and is described in general as thin to thick beds of soft shale, with occasional beds of fine-grained sandstone, all dipping gently to the northwest. The New Brunswick shales weather readily into small fragments and these quickly revert to silt and clay sized particles.

c. Validity

Based upon field observations, the existing engineering data appears valid insofar as the existing structure's configuration and condition. See Section 6 for comment on the structural stability regarding the width/height ratio.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General

On-site inspections of the dam took place on June 14 and 27 and July 19, 1978. Although there are 1968 records of the NJDEP requesting the City of New Brunswick to inspect the dam, no evidence that this inspection was undertaken were available.

b. Dam

The concrete arch is in fairly good condition but appears to be stabilized to a considerable degree by heavy siltation and dumped riprap on both the upstream and downstream sides. There is evidence of minor reconstruction and asphalt patching of the berm on the upstream side of the west abutment. There was no evidence of major fractures, or pieces missing from the crest of the dam. The location or condition of construction joints in the crest arch are unknown as they were underwater at the time of inspection. There is considerable spalling and surficial deterioration of the exposed concrete. The 19 July reinspection was held to verify this condition and the material in the downstream channel.

c. Appurtenant Structures

One of the three 30 inch sluice gates appears to be destroyed but the remaining two are operable to control reservoir elevation for the water intake dam immediately downstream.

d. Reservoir Area

There is a fair amount of debris and several large fallen trees in both the upstream and downstream reservoirs. The Weston Mills Pond extends

several miles up Lawrence Brook to the dam at Farrington Lake but the reservoir width is quite restricted by the relatively steep natural banks and narrow stream channel. Much of the urban contiguous development is well above normal flood elevation.

Judging from the difficulty of access for dredging and the drainage, the inspection confirmed that the upstream reservoir is quite extensively silted.

e. Downstream Channel

The existing banks of lower reservoir between the two dams are also quite steep which, together with the Route 18 concrete arch bridge, seriously restrict the downstream channel hydraulic capacity. Immediately north of the lower dam, the flow is further restricted by a newer bridge (built in 1965) over Burnet Street.

3.2 EVALUATION

The major concern of the inspection team is the status of hydraulic conditions during periods of high flow and collapse possibilities should the dam immediately downstream rupture. From available photographs at the office of the City Engineer, the July 1975 flood did considerable damage to the lower dam water intake structure. Further structural investigation of the concrete spillway, jointery and foundations can only be made if the dam is dewatered (see Section 7).

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

Operational procedures were not observed by the inspection team. Because of the city water supply intake facilities at the dam immediately downstream, city personnel are normally on duty 24 hours a day. From discussions with the City Engineer, operational activity at the Westons Mills Arch dam consist primarily of periodic inspections and the removal of floating drift and debris when the sluice gates are adjusted to control the lower pool intake elevation. Water Department personnel also monitor the dam whenever there are major storms.

4.2 MAINTENANCE OF DAM

The dam is periodically inspected and repairs undertaken when required and funds are available. Several years ago, the dam was inspected by scuba divers and leaks were repaired. Additional riprap was also placed on the downstream side of the spillway.

4.3 MAINTENANCE OF OPERATING FACILITIES

The only operating facilities in use are the two 30 inch gate valves which are periodically inspected by the City.

4.4 DESCRIPTION OF WARNING SYSTEM

None exists except the monitoring by City personnel during major storms.

4.5 EVALUATION

The present operational procedures and safeguards during periods of heavy flows were deemed to be adequate.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

a. Design Data

Utilizing the Guidelines for the Safety Inspection of Dams, it has been determined that the dam at Westons Mills Arch Dam is intermediate in size and falls into the significant hazard category due to the presence of urban development immediately downstream. Accordingly, the spillway design flood (SDF) was determined to be one half the PMF and the inflow hydrograph was calculated from the probable maximum precipitation (PMP).

The entire 200' length of the arch dam functions as a spillway. Abutments on either side of the dam are 24 feet long and 2.5 feet higher than the spillway crest. The maximum discharge over the dam which does not overtop the abutments is 2290 cfs.

The PMF hydrograph for this drainage area was calculated using the SCS curvilinear unit hydrograph. Peak inflow to the reservoir for the PMF and 1/2 PMF was 62,000 cfs and 31,000 cfs respectively, indicating that the discharge capacity of the dam is significantly inadequate. The 1/2 PMF was routed through the reservoir and the discharge decreased insignificantly from 31,000 cfs to 29,000 cfs.

In accordance with Corps of Engineers, Philadelphia District, directives, the inflow hydrograph and flood routing was additionally derived utilizing the HEC-1 program. A slight reduction in the PMF and 1/2 PMF to 58,500 cfs and 29,200 cfs respectively was noted. Flood routing for 1/2 the PMF yielded a peak discharge of 27,340 cfs. Employing the routed SDF, the spillway discharge capacity will accommodate approximately 8% of the SDF.

Since the Lawrence Brook at this location is rather confined in a narrow channel between steep-sided banks, the overtopping discharge capacity was extrapolated to accommodate 1/2 the PMF. It was determined that a flood height 12 feet over the spillway crest (9.5 feet above the abutments) would result during a storm equivalent to 1/2 the PMF (assuming no tailwater control).

b. Experience Data

Although there is no recorded stream flow data immediately downstream from Westons Mills Arch Dam, there is a gaging station 4 miles upstream at the Farrington Dam. Log-Pearson type III flood frequency analyses were performed by the U.S. Geological Survey utilizing weighted WRC map skews on the historical data available from this station. The transposed 100 and 500-year floods are 5800 cfs and 9680 cfs respectively. Floods of these magnitudes would overtop the embankments by approximately 2.0 feet and 3.5 feet respectively. The period of record at Farrington is 50 years. Observations made by City personnel during the storm of July, 1975, (and confirmed by their photographs) indicate the river overtopped the embankments by about 2 to 3 feet. The only discerned damage resulting from that storm was some erosion of the west embankment. This area has since been backfilled with concrete slope protection.

c. Visual Observation

The most westerly of the three sluice gates is destroyed and the usefulness of the remaining sluices is inconsequential during the periods of high flow as they are submerged on both sides of the dam and would have little hydraulic capacity. Therefore, this dam has no drawdown capability.

d. Overtopping Potential

The spillway has a maximum capacity of 8% of the design flood (1/2 PMF) before overtopping the abutments and is clearly inadequate in the significant hazard category. As indicated above, 1/2 the PMF, when routed thru the reservoir, results in a overtopping of the dam by over 9 feet. There is hearsay evidence that this dam has been repeatedly overtopped in the past and the overtopping potential will continue to exist, regardless of the hazard category considered. Due to the present physical geometry, the overtopping potential cannot be related to hazard. However, it is felt that a failure of the dam would not significantly contribute to the downstream water surface elevation (hence the damage potential) as long as the lower dam does not collapse.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

The alignment of the concrete structure is plumb and true and no significant tilting or differential settlements were observed. It is noted that the entire spillway is continuously passing several inches of water hence close visual examination is limited.

b. Design and Construction Data

Referring to Section 2.4.b, only minor cracking and spalling were observed during the field check but because the structure is unreinforced, temperature, rib shortening and shrinkage cracks may be expected in the concrete arch. The reentrant corners of the abutments are deteriorated with the edges broken off but this is of minor consequence.

The original design computations for overturning and sliding stability were unavailable. Maximum concrete stresses appear to have been computed using a three foot hydraulic crest. Although there exists some knowledge of the engineering design techniques employed in 1917, the method actually used for deriving the stability of the dam is extremely questionable in view of the geometry of the structure. The height to base width ratio indicates that some arching action was taken into account in the original design but it appears to have been done on an intuitive basis rather than employing statical methods available in 1917. Based on the SDF head established in this study, the dam appears to be statically unstable and has a negative factor of safety. Without knowledge of the foundation

conditions, further stability investigations in this phase are conjectural.

If the dam is considered to be a gravity structure without arch action it is unstable. Its ability to sustain arch action is directly tied to the contact between the abutment and shale bedrock. Since the New Brunswick shales decompose readily when exposed to air and/or water; further geotechnical explorations must be made to evaluate its present rock supporting capability. It is thought that additional stability is being provided by the downstream face riprap.

c. Operating Records

Performance records are unavailable regarding the dam's stability under maximum loading conditions but it should be noted that the downstream New Brunswick water supply intake dam (just north of Route 18) maintains a tailwater within 4.5 to 5 feet of the spillway crest. The dam appeared to suffer little damage during the July 1975 flood.

d. Post Construction Changes

The only structural modification noted was the raising of the spillway crest by 18 inches during the initial construction (as noted in paragraph 2.2). There is evidence of patching on the structure and riprap has been placed by City forces a few years ago just below the spillway.

e. Seismic Stability

As the dam is located in Seismic Zone 1, little hazard exists from earthquake forces and the potential vulnerability is negligible. The inertial forces relating to Zone 1 earthquake coefficients should be taken into account in the structural analyses in further studies but from the consultant's experience with this type of dam geometry, it will have little effect on the calculated stability and factor of safety compliance relating to the shale foundations.

SECTION 7 - ASSESSMENTS/RECOMMENDATIONS/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Conditions

On the basis of the Phase I visual examination, the existing concrete dam appears to be in fair structural condition and functions adequately as part of the New Brunswick water supply system (although the spillway is extremely inadequate to pass the design flood). No detrimental findings, excepting the physical geometry/design characteristics which, in order to render a complete structural review and analysis, will require the further gathering of information and review, were revealed.

It is believed that the safety of this dam would be substantially decreased if the Lower Dam were to fail. This is due principally to the short 600 foot distance between them which maintains a tailwater on the study dam during overtopping flood conditions.

b. Adequacy of Information

The information gathered for Phase I is thought to be adequate but the available data is insufficient to fully evaluate the structural stability of the dam in detail. This will have to be done in further studies and will require geotechnical investigations of the foundation rock and visual inspection of the spillway and abutments.

c. Urgency

A collapse of the Lower Dam (north of Route 18) could endanger the integrity of the Westons Mills Arch dam by eventually causing a sweepout of the lower stream face channel bed fill material and riprap that is thought to presently help stabilize the dam.

Consequently, further investigations should be undertaken in the near future regarding the foundation conditions and stability of the dam.

d. Necessity for Further Study

The inspection indicates that improvements to the spillway are impractical although its capacity does not meet the requirements of the Recommended Guidelines for Safety Inspection of Dams, passing only 8 percent of the SDF. However, due to the unknown condition of the foundations and the concrete in the spillway structure, additional studies and structural analyses appear to be warranted.

7.2 RECOMMENDATIONS/REMEDIAL ACTIONS

a. Alternatives

Inasmuch as original stability analyses and design computations are unavailable and this dam is classified in the significant hazard category, it is recommended that further studies be undertaken regarding these aspects. It is recommended that the owner provide, at his own expense, stability computations, including a trial arch analysis, and additional investigative data on the foundation conditions. This information is considered essential to complete assess the continued stability and to determine if the dam constitutes a hazard to human life and property. Its structural condition is classified as questionable pending receipt of the further investigations.

Remedial measures recommended are the construction of concrete or riprap slope protection above and below the abutments and to remove the large debris presently in the upstream channel. The berms behind the abutments should be raised to at least the height of the abutments and protected.

b. O&M Maintenance and Procedures

Because the City of New Brunswick presently maintains a close monitoring of the Westons Mills Arch Dam, little is foreseen as improvements to O&M procedures. However, a check list should be developed for periodic maintenance inspections so records of conditions and repairs can be maintained.




FIGURE I
REGIONAL
VICINITY MAP
SCALE 1:24,000




FIGURE 2

SHEET 1

Check List
Visual Inspection
Phase 1

Name Dam Weston Mills Arch Dam County Middlesex State New Jersey Coordinators NJDEP

June 14, 19, 27

Date(s) Inspection July 19, 1978 Weather Clear Temperature 80°

Pool Elevation at Time of Inspection 18.6 M.S.L. Tailwater at Time of Inspection 14.0 M.S.L.

Inspection Personnel:

T. Chapter	<u>K. Jolls</u>
M. Carter	<u>R. Lang</u>
C. Hoffman	<u></u>

K.F. Jolls Recorder

CONCRETE/MASONRY DAMS

SHEET 2

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SEEPAGE OR LEAKAGE	Unknown (entire spillway submerged)	Unreinforced concrete arch. There are some type of joints in structure (unknown)
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Satisfactory. No seepage observed. Left embankment junction patched.	Berms behind abutments should be regraded up to abutment grade.
DRAINS	None	
WATER PASSAGES	None	
FOUNDATION	Unknown. Shale bedrock exists within 10-15 feet of ground. Steep banks indicate rock close to surface.	N. Brunswick Shale area.

CONCRETE/MASONRY DAMS

SHEET 3

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Unknown in spillway. (Continuously submerged)	Concrete very old but only surface is eroded. Appears to be monolithically solid in interior. (Only abutments observed).
STRUCTURAL CRACKING	Unknown in spillway. (Continuously submerged)	
VERTICAL AND HORIZONTAL ALIGNMENT	Satisfactory. No differential settlement observed at top elevations.	Plans indicate foundation is on solid rock.
MONOLITH JOINTS	None observed.	
CONSTRUCTION JOINTS	Poor condition at abutments.	Joint deterioration not critical in abutments Spalling indicates concrete is not reinforced.

EMBANKMENT

SHEET 4

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	N/A	Narrow berms at abutments. Except for slope protection, embankment minor concern re zoning and classification.
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Some erosion. Minor patching with concrete and asphalt at west abutment.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	N/A	
RIPPRAP FAILURES	Riprap dumped in channel. None behind abutments.	

EMBANKMENT

SHEET 5

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	See page 2	
ANY NOTICEABLE SEEPAGE	No	
STAFF GAGE AND RECORDER	None	
DRAINS	None. Drains in concrete spillway only.	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Unknown (continuously submerged)	
INTAKE STRUCTURE	3-30" Ø sluice gates.	2 gates operable. 1 vandalized. Temporary wood catwalk built over gates.
OUTLET STRUCTURE	30" Ø pipes (approximately 9' below spillway crest) at each gate.	
OUTLET CHANNEL	See page 7.	
EMERGENCY GATE	None	No drawdown capability.

UNCATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Narrow crest (3' x 200') on 160' radius. Entire spillway built at same elevation.	Base width to height ratio small for gravity structure. Determine arching effect in further studies.
APPROACH CHANNEL	Natural stream channel confined by natural, rather steep river banks.	
DISCHARGE CHANNEL	See approach canal.	Stability depends on Lower Dam bridge. Danger of sweepout.
BRIDGE AND PIERS	None	

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	N/A	
APPROACH CHANNEL	N/A	
DISCHARGE CHANNEL	N/A	
BRIDGE AND PIERS	N/A	
GATES AND OPERATION EQUIPMENT	N/A	

INSTRUMENTATION

VISUAL EXAMINATION MONUMENTATION/SURVEYS	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
	None	
OBSERVATION WELLS	None	
WEIRS	None	
PIEZOMETERS	None	
OTHER	There is a gage at Farrington dam (4 miles upstream).	Current records are available. New Jersey Water Resources U.S.G.S. Survey NJ-76-1.

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Length extends up Lawrence River approximately 5 miles. Slopes are steep in many areas.	Flow thru reservoir restricted by bridge at Ryder's Lane.
SEDIMENTATION	Unknown. Heavily silted up in upper reaches of pond but not near dam.	Difficult access due to residential areas for dredging and/or silt removal.

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Considerable debris (large trees) in channel.	Route 18 concrete arch bridge between study and lower dam. Minor hydraulic constriction.
SLOPES	Steep natural banks (rock apparently in close to surface).	Trees on sides in many areas.
APPROXIMATE NO. OF HOMES AND POPULATION	Very few homes in zones of flooding. There are boat basins and similar facilities below lower dam.	All residential areas are on sufficient high ground.

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
WESTONS MILLS ARCH DAM

ITEM	REMARKS
PLAN OF DAM	Available for structural geometry; No details available.
REGIONAL VICINITY MAP	Available
CONSTRUCTION HISTORY	Partially available (photographs)
TYPICAL SECTIONS OF DAM	Available
HYDROLOGIC/HYDRAULIC DATA	Available at Farrington Dam gage
OUTLETS - PLAN	None
- DETAILS	
-CONSTRAINTS	
-DISCHARGE RATINGS	
RAINFALL/RESERVOIR RECORDS	Not available

ITEM	REMARKS
DESIGN REPORTS	Not available
GEOLOGY REPORTS	Not available
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None available
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None available
POST-CONSTRUCTION SURVEYS OF DAM	None available
BORROW SOURCES.	Unknown

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	Unknown
HIGH POOL RECORDS	Not available
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	Not available
MAINTENANCE OPERATION RECORDS	Hearsay information from City of New Brunswick.

ITEM	REMARKS
------	---------

SPILLWAY PLAN

Available

SECTIONS


DETAILS

OPERATING EQUIPMENT
PLANS & DETAILS

None available



Downstream view of spillway



Dam downstream of study dam

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: Area = 42.0 square miles

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 18.43 (1050 acre-ft.)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 21.09 (1600 acre-ft.)

ELEVATION MAXIMUM DESIGN POOL: 21.09

ELEVATION TOP DAM: 21.09

CREST: _____

- a. Elevation 18.43
- b. Type Narrow Crest Weir
- c. Width 3 ft.
- d. Length 200 ft.
- e. Location Spillover None
- f. Number and Type of Gates 3 - 18" Ø sluices

OUTLET WORKS: None

- a. Type _____
- b. Location _____
- c. Entrance inverts _____
- d. Exit inverts _____
- e. Emergency draindown facilities None

HYDROMETEOROLOGICAL GAGES: _____

- a. Type Water stage recorder
- b. Location Farrington Dam (4 mi. upstream)
- c. Records 1927 - present

MAXIMUM NON-DAMAGING DISCHARGE: 2290 c.f.s.

BY CH DATE 7-75

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A-1 OF

CHKD. BY DATE

Dam InspectionPROJECT J-225SUBJECT WARTON DAM - PRECIPITATION DATA FOR SYNTHETIC HYDROGRAPH

MPF HYDROGRAPH

Fig 1, P-29 Small Dams - Zone C - New Jersey

PMF 10 sq mi 6 hr duration = 2.6"

Fig 2, P-30 Zone C Drainage Area = 72 sq mi

Rainfall = $.87 \times 2.6 = 2.26$ "

Fig 4 Zone C Distribution of 6 hr rainfall

<u>Time</u>	<u>Dist %</u>	<u>Cumul.</u>	<u>ΔR</u>	<u>R Rearing</u>	<u>Rearing</u>	<u>Runoff</u>	<u>Δ Runoff</u>
	<u>of 6 hr</u>	<u>Runoff</u>		<u>(.87 x 2.6)</u>	<u>Cum.</u>	<u>C.F.S.</u>	
0.5	30	6.78	6.78	0.68	0.68	0	0
1.0	48	10.15	4.07	0.90	1.58	0.10	0.10
1.5	58	13.11	2.26	0.90	2.48	0.45	0.35
2.0	65	14.69	1.58	1.13	3.61	1.10	0.65
2.5	71	16.05	1.36	1.13	4.74	1.85	0.75
3.0	76	17.18	1.13	1.36	6.10	2.90	1.05
3.5	81	18.31	1.13	4.07	10.17	6.40	3.50
4.0	85	19.21	0.90	6.78	16.95	12.80	6.40
4.5	89	20.11	0.90	2.26	19.21	15.00	2.20
5.0	93	21.02	0.91	1.58	20.79	16.40	1.40
5.5	97	21.92	0.90	0.91	21.70	17.40	1.00
6.0	100	22.60	0.68	0.90	22.60	18.20	0.80

$$T_c = \left(\frac{L^2 \times C}{H} \right)^{0.385} \quad L = 11 \text{ mi.} \quad H = 70$$

$$T_c = 8.06 \text{ hr.}$$

$$T_p = \frac{D}{2} + 0.6 T_c = \frac{0.5}{2} + 0.6 (8.06) = 5.09 \text{ hr.}$$

$$T_b = 2.67 \times T_p = 13.58$$

$$q_p = \frac{484 \times A \times Q}{T_p} = 3094 \text{ cfs}$$

Above values utilized in derivation of synthetic hydrograph only.

BY _____ DATE _____

CHKD. BY _____ DATE _____

SUBJECT WESTONS MILL

DAM INSPECTION

HYDROGRAPH

(Triangular Method)

PROJECT C-222

Ar

70,000

60,000

50,000


40,000

30,000

20,000

10,000

0 2 4 6 8 10 12 14 16 18 20



BY CH DATE 1-18

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A 3 OF

CHKD. BY _____ DATE _____

DAM INSPECTION

PROJECT C-222

SUBJECT WESTON MILL DAM

Location - on Lawrence Bk (Tributary of Raritan) at East Brunswick N.J.

Comp. 1917 Height = 17'± DRAINAGE AREA (PLANIMETERED) = 42.0 Mi²

Indicated spillway L = 200' Q = 2290

Dam lies upstream from gravity dam which submerges all but about 6' of Weston Mill Dam.

AREA OF RECREATION POOL = 160 ACRES (PLANIMETERED) × AVG DEPTH (N. BRUNSWICK CITY DAM) = 1050 Acre

MIT Drawing available - Spillway

Shows 200' crest on 160' radius

MA = 1600 "

Abutments 2.5' higher than crest ± 24' long

Δ = 2.5° E DAM

Abutments beyond dam - Foundation - ON ROCK

Size - Intermediate Hazard - Significant

Hydrograph 1/2 PMF to PMF

Log Pearson Frequency Q
(@ FARRINGTON DAM)

50 yr = 3770


TRANSPOSED
Q'S

100 yr = 4760 × 1.22 = 5800 cf

Area_{FARR} = $\frac{42.0}{34.1} = 1.22$

502 yr = 7930 × 1.22 = 9680 cf

Spillway discharges



over main crest - L = 200'

H	C	Q
0.5	2.9	205
1.0	2.9	580
1.5	2.9	1065
2.0	2.9	1640
2.5	2.9	2293
3.0	2.9	3014
3.5	2.9	3798
4.0	2.9	4640
5.0	2.9	6485
6.0	2.9	8525
8.0	2.9	13124
10.0	2.9	18341
12.0	2.9	24110
13.0	2.9	27185
14.0	2.9	30382

Over Abutments

H	C	Q	Total Q
			205
			580
			1065
			1640
0	2.5	0	2293
0.5	"	47	3061
1.0	"	134	3932
1.5	2.8	247	4887
2.5		531	7016
3.5		880	9405
5.5		1733	14857
7.5		2760	21100
9.5		3925	28045
10.5		4323	31358
11.5		5242	35624

Surcharge Capacity

Elevation	Area	Ave Area	Δ Vol	Σ Vol
18.43				
30	280		3240	3240

BY TS DATE 2-78 LOUIS BERGER & ASSOCIATES INC. SHEET NO. 11 OF 11
 CHKD. BY LAH DATE 11/25/85 PROJECT C-222
 SUBJECT Precipitation data for input to HEC-1

From "Small Dams":

$$PMF \text{ for } 10 \text{ sq mi} = 26" / 6 \text{ hr.};$$

$$\text{Reduction factor for } 42 \text{ sq mi} = 87\%$$

$$\text{thus: } .87 \times 26" = 22.6" \text{ rainfall}$$

Zone C distribution of 6 hr rainfall

Time	Dist %	Cumal. R.	L.R.	R. Rearing	Rearing Cum	Runoff S.N. 70	L. Rerun.
1	48	10.85	10.85	1.58	1.58	0.10	0.10
2	65	14.69	3.84	2.03	3.61	1.10	1.0
3	76	17.18	2.49	2.49	6.10	2.90	1.8
4	85	19.21	2.03	10.85	16.95	12.80	9.9
5	93	21.02	1.81	3.84	20.79	16.40	3.6
6	100	22.60	1.58	1.81	22.60	18.2	1.8

$$T_c = \left(\frac{(11.9 \times L^2)^{.375}}{11} \right) \quad L = 1 \text{ mi.} \quad V = 70$$

$$T_c = 8.06 \text{ hr.}$$

Alternate determination of T_c per U.S. Army TR-55

$$\text{Channel slope} = \frac{70 \times 100}{11 \times 5280} = 0.12\%$$

$$\text{min. avg. vel. for slopes } < 2\% = 2 \text{ ft/sec}$$

$$\frac{11 \times 5280}{2 \times 3600} = 8.07 \text{ hr}$$

BY H.G. DATE _____

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A5 OF _____

CHKD. BY _____ DATE _____

WESTONS MILL DAMPROJECT C-222SUBJECT DIMENSIONLESS UNITGRAPH (1 HR)

$$\text{Unit Time } T_y = 1 \text{ hr}; \quad T_y = 5.09 \text{ hrs}; \quad L + \frac{D}{2} = \frac{5.09}{0.81} = 6.93 = T$$

$$\text{Area} = 26.89 \text{ mi}^2 \quad \text{DSF (2 in)} = 26.89 \times A = 1129.4$$

<u>Time</u>	<u>% T_y</u> <u>100/T_y (hr)</u>	<u>Dimensionless *</u> <u>Ordinate Q/T_yDSF</u>	<u>Q</u> <u>DSF/T_y (D.O.)</u>
1	14.43	0.9	147
2	28.85	4.2	684
3	43.29	9.2	1500
4	57.72	15.5	2526
5	72.15	19.6	3194
6	86.6	20.9	3406
7	101	19.6	3194
8	115	16.6	2705
9	130	13.2	2151
10	144	10.5	1711
11	159	8.2	1336
12	173	6.5	1059
13	188	5.0	815
14	202	3.8	619
15	216	3.0	489
16	231	2.28	372
17	245	1.68	274
18	260	1.3	212
19	274	1.0	163
20	289	0.78	127
21	303	0.6	95
22	317	0.4	65
23	332	0.3	49
24	346	0.28	45
25	361	0.23	38
26	375	0.2	33
27	390	0.17	27
28	404	0.14	23
29	418	0.11	18

* Value for Dimensionless Ordinate read from graph

BY H. G. DATE _____

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A6

CHKD. BY _____ DATE _____

PROJECT C222

SUBJECT BUREAU OF RECLAMATION DEFINITION OF TERMS USED IN UNITGRA

L, LAG TIME AS DEFINED BY THE SCS IS THE TIME IN HOURS FROM THE MID OF EXCESS RAINFALL, TO THE TIME OF PEAK DISCHARGE.

L, LAG TIME AS DEFINED BY THE BUREAU OF RECLAMATION IS FROM THE CENTER OF MASS OF RAINFALL TO THE CENTER OF MASS OF RUNOFF.

E IS EQUAL TO $\left(\frac{11.9 L^3}{H}\right)^{0.385}$ FROM THE CALIFORNIA CULVERTS PRACTICE

SCS L IS APPROXIMATELY 0.6 T_c

EXAMPLES OF DETERMINING L (LAG) BY BUREAU OF RECLAMATION DEFINITION,

$$L = \frac{T_p - (D/2)}{0.85} \quad \text{WHERE } D \text{ IS THE TIME INTERVAL OF THE UNITG}$$

THE SCS CURVELINEAR UNIT HYDROGRAPH CAN BE DERIVED BY FIRST TAKING BUREAU OF RECLAMATION L, (LAG) PLUS $\frac{D}{2}$ AFTER BEING DIVIDED BY 100, THEN

MULTIPLIED BY EACH ABSCISSA (IN HOURS) BY THE QUOTIENT. THEN READING THE DIMENSIONLESS ORDINATE FOR THE GIVEN PERCENTAGES FROM THE PREVIOUSLY DETERMINED SCS CURVELINEAR DIMENSIONLESS GRAPH, (COPY ATTACHED)

TO OBTAIN Q IN CFS FOR EACH ORDINATE MULTIPLY EACH DIMENSIONLESS ORDINATE BY A FACTOR OBSERVED FOR ONE INCH,


$$26.89 \times \text{AREA}$$

A7

7.	0	1	2	3	4	5	6	7	8	9
0	60	60	61	61	62	62	63	63	63	64
10	64	65	66	67	67	68	68	69	69	70
20	70	71	72	73	74	74	75	75	76	77
30	77	78	79	80	81	81	82	82	83	84
40	84	85	86	87	88	88	89	89	90	91
50	91	92	93	94	95	95	96	96	97	98
60	98	99	100	101	102	102	103	103	104	105
70	105	106	107	108	109	109	110	110	111	112
80	112	113	114	115	116	116	117	117	118	119
90	119	120	121	122	123	123	124	124	125	126
100	126	127	128	129	130	130	131	131	132	133
110	133	134	135	136	137	137	138	138	139	140
120	140	141	142	143	144	144	145	145	146	147
130	147	148	149	150	151	151	152	152	153	154
140	154	155	156	157	158	158	159	159	160	161
150	161	162	163	164	165	165	166	166	167	168
160	168	169	170	171	172	172	173	173	174	175
170	175	176	177	178	179	179	180	180	181	182
180	182	183	184	185	186	186	187	187	188	189
190	189	190	191	192	193	193	194	194	195	196
200	196	197	198	199	200	200	201	201	202	203
210	203	204	205	206	207	207	208	208	209	210
220	210	211	212	213	214	214	215	215	216	217
230	217	218	219	220	221	221	222	222	223	224
240	224	225	226	227	228	228	229	229	230	231
250	231	232	233	234	235	235	236	236	237	238
260	238	239	240	241	242	242	243	243	244	245
270	245	246	247	248	249	249	250	250	251	252
280	252	253	254	255	256	256	257	257	258	259
290	259	260	261	262	263	263	264	264	265	266
300	266	267	268	269	270	270	271	271	272	273
310	273	274	275	276	277	277	278	278	279	280
320	280	281	282	283	284	284	285	285	286	287
330	287	288	289	290	291	291	292	292	293	294
340	294	295	296	297	298	298	299	299	300	301
350	301	302	303	304	305	305	306	306	307	308
360	308	309	310	311	312	312	313	313	314	315
370	315	316	317	318	319	319	320	320	321	322
380	322	323	324	325	326	326	327	327	328	329
390	329	330	331	332	333	333	334	334	335	336
400	336	337	338	339	340	340	341	341	342	343
410	343	344	345	346	347	347	348	348	349	350
420	350	351	352	353	354	354	355	355	356	357
430	357	358	359	360	361	361	362	362	363	364
440	364	365	366	367	368	368	369	369	370	371
450	371	372	373	374	375	375	376	376	377	378
460	378	379	380	381	382	382	383	383	384	385
470	385	386	387	388	389	389	390	390	391	392
480	392	393	394	395	396	396	397	397	398	399
490	399	400	401	402	403	403	404	404	405	406
500	406	407	408	409	410	410	411	411	412	413

SUMMARY OF HYDRAULIC CHARACTERISTICS

AS



BY TC DATE _____

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A9 OF _____

CHKD. BY _____ DATE _____

Dam InspectionPROJECT C-222SUBJECT Storage / Discharge Summary Sheet

<u>Elev (Ft. Above Crest)</u>	<u>Storage (Acrc ft.)</u>	<u>Discharge (cfs)</u>
1	275	580
2	550	1640
3	825	3061
4	1100	4887
5	1400	7016
6	1675	9405
7	1950	12750
8	2250	14857
9	2525	18600
10	2800	21100
11	3090	24500
12	3370	28045

FINAL RUN

IIIMX7-30/IIIMX/IIIM ACSEPI

NOTIFICATION - OF

	NR	NIN	DAY	IIR	IWIN	METRC	IPLI	IPRT	NSIAN
NO									
100	1	0	0	0	0	0	0	0	0

00389 Vdr
6

SUB-AREA RUNOFF COMPUTATION.

SECRET - NOFORN

ISTAG	ICOMP	IECON	ITAPE	JPLY	JPRT	IVAME
5	0	0	0	2	0	1

HYDROGRAPH DATA

	INSTR	TREAS	SWAP	FUTURA	TRD/C	RATIO	ISNR	ISMT	LOCAL
0	-1	42.00	0.6	42.00	0.0	0.500	0	0	0

PRECIP DATA

NO	STORY	DAJ	DAK
5	0.0	0.0	0.0

PRECIP PATTERN

LOSS DATA

STAGE	CLIP	RTOL	ERR	STRES	RICH	STATL	CNSTL	ALSMX	RTIMP
0.0	0.0	1.00	0.0	0.0	1.00	0.0	0.0	0.0	0.0
1.0	0.0	1.00	0.0	0.0	1.00	0.0	0.0	0.0	0.0

EVEN UNIT GRAPH. UJHGQ = 29

147.	484.	1800.	2225.	2154.	3406.	3194.	2705.	2151.	1711.
148.	1552.	215.	419.	649.	372.	274.	212.	163.	127.
149.	65.	40.	45.	24.	55.	27.	23.	18.	

RECEIVED DATE

```

0 2RCSN= 0.0 PRIOR= 1.00
REGRESSION DATA

```

75-501838-36-CN3

TIME RAILY EXES COMB O

15.

215.

1099-
• 572

4477
1099 •

7457.
12466.

● 2007

• 46117

•

55007 •

56454 •

●●●●●

Downloaded At: 11:53 11 September 2009

A 10

72	0.0	0.0	0.0
73	0.0	0.0	0.0
74	0.0	0.0	0.0
75	0.0	0.0	0.0
76	0.0	0.0	0.0
77	0.0	0.0	0.0
78	0.0	0.0	0.0
79	0.0	0.0	0.0
80	0.0	0.0	0.0
81	0.0	0.0	0.0
82	0.0	0.0	0.0
83	0.0	0.0	0.0
84	0.0	0.0	0.0
85	0.0	0.0	0.0
86	0.0	0.0	0.0
87	0.0	0.0	0.0
88	0.0	0.0	0.0
89	0.0	0.0	0.0
90	0.0	0.0	0.0
91	0.0	0.0	0.0
92	0.0	0.0	0.0
93	0.0	0.0	0.0
94	0.0	0.0	0.0
95	0.0	0.0	0.0
96	0.0	0.0	0.0
97	0.0	0.0	0.0
98	0.0	0.0	0.0
99	0.0	0.0	0.0
100	0.0	0.0	0.0

SUM 18.20 18.20 492854.

CEG	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
10-45	50135.	20278.	5845.	492854.
AC-PT	11.10	10.05	18.19	18.19
	24372.	40440.	40753.	40753.

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(O)

A 13

INFLUX(I), OUTFLOW(O) AND OBSERVED FLOW(O)

[illegible]

A 14

STILLING COTTAGE

ITEM	QTY	UNIT	PRICE	TOTAL	TAX	STRT
ITEM 1	1	UNIT	0.00	0.00	0.00	0.00
ITEM 2	1	UNIT	0.00	0.00	0.00	0.00
ITEM 3	1	UNIT	0.00	0.00	0.00	0.00
ITEM 4	1	UNIT	0.00	0.00	0.00	0.00
ITEM 5	1	UNIT	0.00	0.00	0.00	0.00
ITEM 6	1	UNIT	0.00	0.00	0.00	0.00
ITEM 7	1	UNIT	0.00	0.00	0.00	0.00
ITEM 8	1	UNIT	0.00	0.00	0.00	0.00
ITEM 9	1	UNIT	0.00	0.00	0.00	0.00
ITEM 10	1	UNIT	0.00	0.00	0.00	0.00
ITEM 11	1	UNIT	0.00	0.00	0.00	0.00
ITEM 12	1	UNIT	0.00	0.00	0.00	0.00
ITEM 13	1	UNIT	0.00	0.00	0.00	0.00
ITEM 14	1	UNIT	0.00	0.00	0.00	0.00
ITEM 15	1	UNIT	0.00	0.00	0.00	0.00
ITEM 16	1	UNIT	0.00	0.00	0.00	0.00
ITEM 17	1	UNIT	0.00	0.00	0.00	0.00
ITEM 18	1	UNIT	0.00	0.00	0.00	0.00
ITEM 19	1	UNIT	0.00	0.00	0.00	0.00
ITEM 20	1	UNIT	0.00	0.00	0.00	0.00
ITEM 21	1	UNIT	0.00	0.00	0.00	0.00
ITEM 22	1	UNIT	0.00	0.00	0.00	0.00
ITEM 23	1	UNIT	0.00	0.00	0.00	0.00
ITEM 24	1	UNIT	0.00	0.00	0.00	0.00
ITEM 25	1	UNIT	0.00	0.00	0.00	0.00
ITEM 26	1	UNIT	0.00	0.00	0.00	0.00
ITEM 27	1	UNIT	0.00	0.00	0.00	0.00
ITEM 28	1	UNIT	0.00	0.00	0.00	0.00
ITEM 29	1	UNIT	0.00	0.00	0.00	0.00
ITEM 30	1	UNIT	0.00	0.00	0.00	0.00
ITEM 31	1	UNIT	0.00	0.00	0.00	0.00
ITEM 32	1	UNIT	0.00	0.00	0.00	0.00
ITEM 33	1	UNIT	0.00	0.00	0.00	0.00
ITEM 34	1	UNIT	0.00	0.00	0.00	0.00
ITEM 35	1	UNIT	0.00	0.00	0.00	0.00
ITEM 36	1	UNIT	0.00	0.00	0.00	0.00
ITEM 37	1	UNIT	0.00	0.00	0.00	0.00
ITEM 38	1	UNIT	0.00	0.00	0.00	0.00
ITEM 39	1	UNIT	0.00	0.00	0.00	0.00
ITEM 40	1	UNIT	0.00	0.00	0.00	0.00
ITEM 41	1	UNIT	0.00	0.00	0.00	0.00
ITEM 42	1	UNIT	0.00	0.00	0.00	0.00
ITEM 43	1	UNIT	0.00	0.00	0.00	0.00
ITEM 44	1	UNIT	0.00	0.00	0.00	0.00
ITEM 45	1	UNIT	0.00	0.00	0.00	0.00
ITEM 46	1	UNIT	0.00	0.00	0.00	0.00
ITEM 47	1	UNIT	0.00	0.00	0.00	0.00
ITEM 48	1	UNIT	0.00	0.00	0.00	0.00
ITEM 49	1	UNIT	0.00	0.00	0.00	0.00
ITEM 50	1	UNIT	0.00	0.00	0.00	0.00
ITEM 51	1	UNIT	0.00	0.00	0.00	0.00
ITEM 52	1	UNIT	0.00	0.00	0.00	0.00
ITEM 53	1	UNIT	0.00	0.00	0.00	0.00
ITEM 54	1	UNIT	0.00	0.00	0.00	0.00
ITEM 55	1	UNIT	0.00	0.00	0.00	0.00
ITEM 56	1	UNIT	0.00	0.00	0.00	0.00
ITEM 57	1	UNIT	0.00	0.00	0.00	

STAGE =	0	0	270	350	470	1110	1400	1675	3090	3370
CURLO =	0	0	500	1340	3051	4837	7015	7405	24000	24045

Yr	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
Yr	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
472	1	5	29	129	427	1001	1775	2524	3063	3514	3882	4053	2740	2637	2037	1835	1596	1392	1217	1059	920	801	693	610	532	482	402	333	283	240	201	165	140	117		
SIZE	1	5	29	129	427	1001	1775	2524	3063	3514	3882	4053	2740	2637	2037	1835	1596	1392	1217	1059	920	801	693	610	532	482	402	333	283	240	201	165	140	117		
AVG	7	59	328	1284	4221	9826	16593	23531	27861	26814	26737	27957	19300	14784	11537	9109	7042	5437	4195	3192	2419	1847	1413	1091	813	595	465	390	324	283	233	183	164	15	8	0
IN	7	59	328	1284	4221	9826	16593	23531	27861	26814	26737	27957	19300	14784	11537	9109	7042	5437	4195	3192	2419	1847	1413	1091	813	595	465	390	324	283	233	183	164	15	8	0
POP	000	10	52	278	1173	4176	10474	18463	28214	27739	28225	24171	20762	17104	13759	10913	8663	6966	5676	4552	3645	2915	2396	1944	1571	1307	1079	892	741	617	540	481	420	357	300	261
OUT	000	10	52	278	1173	4176	10474	18463	28214	27739	28225	24171	20762	17104	13759	10913	8663	6966	5676	4552	3645	2915	2396	1944	1571	1307	1079	892	741	617	540	481	420	357	300	261

40	51.	0.	123.
41	43.	0.	103.
42	60.	0.	66.
43	53.	0.	72.
44	28.	0.	60.
45	28.	0.	51.
46	20.	0.	42.
47	17.	0.	35.
48	13.	0.	30.
49	12.	0.	25.
50	10.	0.	21.
51	8.	0.	17.
52	7.	0.	15.
53	6.	0.	12.
54	3.	0.	10.
55	4.	0.	9.
56	3.	0.	7.
57	3.	0.	6.
58	2.	0.	5.
59	2.	0.	4.
60	2.	0.	4.
61	1.	0.	3.
62	1.	0.	2.
63	1.	0.	2.
64	1.	0.	2.
65	1.	0.	1.
66	1.	0.	1.
67	0.	0.	1.
68	0.	0.	1.
69	0.	0.	1.
70	0.	0.	1.
71	0.	0.	0.
72	0.	0.	0.
73	0.	0.	0.
74	0.	0.	0.
75	0.	0.	0.
76	0.	0.	0.

246429.

	FIK	4-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CES	27359.	23546.	10045.	3423.	246429.
INCHES		5.24	8.90	9.10	9.10
AC-FI		11731.	19934.	20376.	20376.

5000

STATION 50

	4000.	8000.	12000.	16000.	20000.	24000.	28000.	32000.	0.	0.	0.	0.	0.
1													
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													
14													
15													
16													
17													
18													
19													
20													
21													
22													
23													
24													
25													
26													
27													
28													
29													
30													
31													
32													
33													
34													
35													
36													
37													
38													
39													
40													
41													
42													
43													
44													
45													
46													
47													
48													
49													
50													
51													
52													
53													
54													
55													
56													
57													
58													
59													
60													
61													
62													
63													
64													
65													
66													
67													
68													
69													
70													
71													
72													
73													
74													
75													
76													
77													
78													
79													
80													
81													
82													
83													
84													
85													
86													
87													
88													
89													
90													
91													
92													
93													
94													
95													
96													
97													
98													
99													
100													

BUNGE SUMMARY, AVERAGE FLOW				
HYDROGRAPH AT	5	24217.	25057.	26644.
ROUTED TO	55	27339.	10195.	10045.
		6-HOUR	24-HOUR	72-HOUR
		AREA	AREA	AREA
		42.00	3423.	5423.
		42.00	42.00	42.00

A17